STATE OF ALASKA

DEPARTMENT OF NATURAL RESOURCES



DIVISION OF MINING, LAND AND WATER DAM SAFETY AND CONSTRUCTION UNIT

Certificate of Approval to Modify a Dam

The **State of Alaska** under Alaska Statute Title 46 and the regulations adopted under this statute, grants to:

Teck Alaska Incorporated

The approval to modify the following structure at the **Red Dog Mine** in accordance with the terms and conditions contained in this certificate:

Red Dog Tailings Back Dam (NID ID# AK00303)

The location of this project is: S31, T31N, R18W, Kateel River Meridian

The holder of this certificate shall:

_	documents listed in Attachment A.
	Except for claims or losses arising from negligence of the State, defend and indemnify the State against, and hold it harmless from any and all claims, demands, legal actions, loss, liability and expense for injury or death of persons, and damages to or loss of property, arising out of or connected with the exercise of the approval granted by this certificate.
	Comply with all applicable laws, regulations and conditions.
	Allow representatives of the Department to inspect the work and records covered by this certificate at all times determined necessary by the Commissioner.
	Follow special conditions listed in Attachment B, attached hereto and made a part hereof.

This *Certificate of Approval to Modify a Dam* is granted subject to the pertinent statutory provisions in AS 46.17 and the Administrative Regulations in 11 AAC 93. This certificate is valid only for the time period indicated in Attachment B.

Charles F Cobb P F

,	
TITLE:	State Dam Safety Engineer Division of Mining, Land and Wate
SIGNATURE: DATE:	Gune 24, ror1
State of Alaska)
Third Judicial District) SS.)

APPROVED BY:

This is to certify that on ______, 2021, before me appeared <u>Charles F. Cobb</u>, known by me to be the Authorized Representative of the Division of Mining, Land and Water, Alaska Department of Natural Resources, and acknowledged to me that this Certificate of Approval was voluntarily executed on behalf of the State of Alaska.

Notary Public in and for the State of Alaska

My Commission expires:

OFFICIAL SEAL Christine Ballard Notary Public - State of Alaska My Commission Expires with Office

Attachment A – Approved Construction Documents

DRAWINGS Teck Alaska Incorporated

Tailings Back Dam Stage V Raise

Red Dog Mine, Alaska

Stage V Raise to Elevation 1006 Feet Marked "ISSUED FOR CONSTRUCTION"

Drawing Number	Revision	Title	Date
001	0	Cover Sheet	5/27/2021
002	0	Initial Construction Conditions	5/27/2021
003	0	Stage V Excavation Plan	5/27/2021
004	0	Stage V Embankment Grading Plan (1 of 2)	5/27/2021
005	0	Stage V Embankment Grading Plan (2 of 2)	5/27/2021
006	0	Typical Embankment Section	5/27/2021
007	0	Stage V Cut-Off Wall Profile	5/27/2021
800	0	Cut-Off Wall Details	5/27/2021

SPECIFICATIONS Specifications for

Construction of Tailings Back Dam

Stage V Raise

Red Dog Mine - Alaska Rev. 0, dated 5/27/2021

Marked "ISSUED FOR CONSTRUCTION"

CONSTRUCTION Tailings Back Dam Stage V Raise

QUALITY

Red Dog Mine Alaska

ASSURANCE PLAN Construction Quality Assurance Plan

Rev. 0, dated 5/27/2021

Marked "ISSUED FOR CONSTRUCTION"

End of Attachment A

<u>Attachment B – Special Conditions</u>

- 1. This certificate approves the modification of the Red Dog Tailings Back Dam cut-off wall and embankment from its current nominal crest elevation at 996.5 feet to a nominal crest elevation of 1006.5 feet in two stages referred to as Stage V-A and Stage V-B, plus insulation and limited cover fill. The work must be completed as indicated in the construction documents listed in Attachment A.
- 2. During the modification and after construction is complete, the Red Dog Tailings Back Dam is to be operated as a Class I (high) hazard potential classification dam as defined in 11 AAC 93.157.
- 3. All work associated with the modification of the dam and appurtenant works must be observed and inspected by an engineer qualified in accordance with 11 AAC 93.193(c) for compliance with the approved drawings, specifications and construction quality assurance/quality control documents listed in Attachment A, and for developing the construction completion report required under Special Condition 6.
- 4. Any fill containing more than 5% fines passing the #200 sieve may not be placed under freezing conditions.
- 5. If any conditions are encountered which require substantial clarification, deviation or change in the design from the approved drawings and specifications, the clarification, deviation or change must be approved in writing by the design engineer and submitted to the Department. Any clarification, deviation or change that could affect the safety of the dam must be approved in writing by the Department before continuing that aspect of construction. The design engineer shall maintain a sequentially numbered record of all clarifications, deviations and changes in the design and construction for inclusion in the construction completion report required under Special Condition 6.
- 6. No water or tailings may be impounded or deposited against the raised section of the Red Dog Tailings Back Dam until a *Certificate of Approval to Operate a Dam* is issued by the Department. The Department will issue a *Certificate of Approval to Operate a Dam* including any pertinent terms and conditions, upon review and approval of the following submittals:
 - ☐ Construction completion report prepared in accordance with the requirements of 11 AAC 93.171(f)(6)(A) including design change details and approvals for each stage of completion
 - ☐ A current operation and maintenance manual prepared in accordance with the requirements of 11 AAC 93.197 for each stage of operation
 - □ A current emergency action plan developed in accordance with the requirements of 11 AAC 93.164(e).
- 7. Notify the Department within one week after the date of substantial completion of each stage of completion. Submit the post-construction documentation listed under Special Condition 6 within approximately 60 days of substantial completion.

- 8. Any existing instrumentation potentially affected by this modification must be preserved and remain operational, or be replaced, unless specifically approved for removal or abandonment by the design engineer and the Department.
- 9. Commence construction by the first day of June of the second calendar year after the date of this certificate. If construction does not begin by this date, an updated application must be submitted for review and approval by the Department, including application fees required under 11 AAC 05.010.
- 10. Requirements for post-closure operation including seepage management and instrumentation monitoring must be included in the financial assurance required under Special Condition 11.
- 11. No later than December 31, 2021, provide adequate financial assurance required by 11 AAC 93.171(f)(2)(C) and 11 AAC 93.172(a)(6)(C) must be demonstrated for the following:
 - Modification of the Red Dog Tailings Back Dam and appurtenant works to a final, post-closure operating configuration including consideration for premature closure
 - □ Post-closure monitoring, operation, maintenance, and inspection of the dam and appurtenant works, as necessary

The specific tasks and cost estimates may be included as discrete line items in the reclamation and closure plan required under 11 AAC 97.310. The methods of financial assurance, the proposed final, post-closure configuration, the post-closure monitoring, operation, maintenance and inspection requirements, the respective cost estimates and the schedule for posting the financial assurance are subject to approval by the Department. The Department's approval may be withdrawn, and additional financial assurance may be required, if the Department determines that circumstances at the mine or otherwise so require.

- 12. Unless completed under provisions for design changes in Special Condition 5, no later than December 31, 2021, submit a plan and schedule to address outstanding recommendations of the engineer of record included in the report *Detailed Design Tailings Back Dam Stage V—Crest Elevation 1,006 Feet* by Golder Associates dated April 12, 2021. This includes additional seepage collection wells described and recommended in Appendix C and instrumentation described and recommended in Appendix G of the cited report.
- 13. No later than January 31, 2022, submit an updated construction schedule for the Stage V-B raise to nominal elevation 1006 ft.
- 14. This certificate of approval expires on June 2, 2023.

End of Attachment B

D/F:daminfo/projects/reddog/backdam/certificates/COAMOD FY2021-30-AK00303