Teck Alaska, Inc. - Red Dog Mine 4th Quarter & Annual Report 2017 Waste Management Permit No. 2016DB0002 Reclamation Plan Approval F20169958 March 1st, 2018

Table of Contents

Introduction	4
Annual Summary of Biomonitoring Water Quality Sampling	
Permafrost and Sub-permafrost Groundwater MonitoringPermafrost and Subsurface Temperature Monitoring	4
Mine Water ManagementMine water flows	
Mine water quality	5
Mine Water Quality Trend Charts	5
Visual Monitoring of Mine Water Management Systems	5
Water and Load Balance	6
Significant activities in mine water management	6
Waste Rock ManagementQuantities, placement locations and analysis of waste rock	
Results of waste rock geochemical monitoring	7
Visual monitoring of waste rock facilities	7
Significant activities in waste rock management	9
Tailings ManagementQuantities and analysis of tailings	
Tailings Storage Facility and Main Pit Dump water elevation	10
Visual monitoring of tailings facilities	10
Significant activities in tailings management	10
Class III Municipal Solid Waste Landfill	
Quantities of inert solid waste for the reporting year	13
Significant activities in solid waste landfill	13
Mining and Milling Activities	
Milling Quantities	13
Significant activities in mining and milling	14
Reclamation	14
Reclamation Research	14
Reclamation Monitoring	14
Significant reclamation activities	14
Dust	
Dust monitoring activities	
Wildlife interactions	
Financial Assurance	14

List of Tables & Figures	
Table 1 - Water Management Volumes	5
Table 2 - Cover Material Amount	
Table 3 - Tailings Generated	9
Table 4 - Tailings Storage Facility and Main Pit water elevations	
Table 5 - Ore Mined	13
Table 6 - Ore Processed through Mill	13
Table 7 - Area Disturbed in 2017	14
Figure 1 - Photos of MWD Synthetic Cover Project	7
Figure 2 - Tailings Storage Facility Bathymetry Map	11
Figure 3 - Main Pit Bathymetry Map	12
Figure 4 - Land Disturbance Map	
Appendixes	
Appendix A: Permafrost and Sub-permafrost Groundwater Monitoring Annual Report (pending March)	ı, 1 st week
Appendix B: Water Quality Profile II Charts – Mine Water Monitoring Stations	
Appendix C: Water Quality Profile I Charts – Mine Drainage Monitoring Stations	
Appendix D: Water Quality Profile I Charts – Bons Creek Monitoring Stations	
Appendix E: Water Quality Profile I Charts – APDES Monitoring Stations	
Appendix F: Waste Rock Production Summary	
Appendix G: Cover Material Stockpile Summary	
Appendix H: Red Dog One Year Mine Plan 2018	
Appendix I: Red Dog Mine Water and TDS Mass Balance	
Appendix J: Risk Management Plan (RMP) Fugitive Dust (pending, 2 nd quarter)	

Introduction

This report has been prepared to fulfill the 4th quarter and annual reporting requirements of Teck Alaska Incorporated's (TAK) obligations under the State of Alaska Waste Management Permit No. 2016DB0002 and the Red Dog Mine Reclamation Plan Approval F20169958.

This report addresses mine water management, biomonitoring, waste rock management, tailings management, permafrost and groundwater monitoring, water load balance, Class III waste landfill, mining and milling activities, reclamation activities, land disturbance and wildlife interactions for the reporting period.

Biomonitoring Program

Annual Biomonitoring Report

The annual biomonitoring report will be submitted with the 2018 2nd quarter report.

Annual Summary of Biomonitoring Water Quality Sampling

Analytical results of samples collected for biomonitoring water quality are attached with the electronic file, *Red Dog 2017 Analytical Results Profile I.xlsx*. Biomonitoring sampling ended for the year on October 9, 2017. Analytical samples were collected from both the Bons Creek and Mine Drainage Monitoring areas and analyzed for constituents listed in Table 2 – Profile I of the "Monitoring Plan, Aug 2016".

Permafrost and Sub-permafrost Groundwater Monitoring

Permafrost and Subsurface Temperature Monitoring

Piezometer and thermistor recordings were completed for the 4th quarter per the SEP requirements. The 2017 annual for the Permafrost and Groundwater Monitoring Program report is included within this report under Appendix A.

Significant activities in Permafrost and Sub-permafrost Groundwater Monitoring

Piezometer well P97-013 which is located on the Kivalina overburden stockpile is scheduled to be replaced during 2018. The existing piezometer lost nitrogen pressure at the inflator which has led to erroneous readings. A design plan for the new replacement well will be submitted to EPA Region 10 for approval prior to replacing the existing well. Well replacement updates will be included with the 2018 quarterly reports.

Mine Water Management

Mine water flows

Table 1 lists mine water volumes transferred from mine areas during the reporting period. The table also includes a summation of volumes transferred for the report year. All flow monitoring stations operated normally with no problems noted for the period.

The facility ceased discharging from Outfall 001 on September 23rd. Approximately 1.89 billion gallons were discharged during the reporting period from outfall 001.

Table 1 - Water Management Volumes

	Volume in Gallons				
Mine Water Monitoring Stations	October	November	December	2017 Total	
Bon's Creek Total Flow	13,080,000	14,060,000	13,680,000	182,404,000	
Mine Water Sump Total Flow ¹	70,270,000	62,420,000	36,310,000	773,610,000	
Main Dam Seepage Pumpback	29,390,000	27,220,000	25,600,000	454,410,000	
Reclaim Flow to Mill	238,800,000	225,700,000	263,200,000	3,359,700,000	
WTP #1 Influent from Reclaim	869,900	2,323,000	0	348,256,410	
WTP #1 Influent from Mine Sump	4,061	0	20,830,000	20,834,061	
WTP #1 Clarifier Sludge To Tails	0	0	0	109,157	
WTP #2 Influent from Reclaim	0	0	0	2,567,070,000	
WTP #2 Sludge To Tails	432,000	0	0	46,628,393	
Discharge to Red Dog Creek	0	0	0	1,891,084,261	
WTP #3 Influent from MWD	6,695,000	4,489,000	3,825,000	56,662,000	
WTP #3 Influent from Mine Sump	0	0	0	2,984,000	
WTP #3 Total Effluent	6,695,000	0	0	59,646,000	
East Overburden Sump	3,352,900	622,900	380,200	14,366,700	
West Overburden Sump	545,300	1,149,100	7,700	15,049,800	
Main Waste ARD to Main Pit	0	0	0	2,461,300	
Treated Water to Main Pit	0	0	0	0	
Tailings Water Supernatant (calc.)	203,949,000	233,310,000	239,599,000	2,758,091,000	

Notes: ¹ Includes Main Pit water pumped back to Tailings Storage Facility

Mine water quality

Mine water quality charts were reviewed during the 4th quarter, during this review it was noted for both the East and West overburden sumps analytical results for dissolved copper have been omitted from testing since August 2015. It was determined the missed testing was due to the Chain of Custody (COC) forms completed after July 2015 did not list dissolved copper, thus the lab did not test this constituent. The electronic COC's have since been corrected. The missed data is not expected to have any impact from either area.

Mine Water Quality Trend Charts

Mine water quality trend charts are provided in Appendixes B, C, D, and E of this report. Water quality Profile I and II ("Monitoring Plan, Aug 2016") constituents for the Mine Water, Mine Drainage, Bons Creek and APDES stations are illustrated for a five year period ending with the 4th quarter. Trend charts depict the Water Quality Standard (WQS) when applicable.

Visual Monitoring of Mine Water Management Systems

Red Dog diversion ditches, seepage collection and treated water discharge lines were monitored during the quarter. All mine water systems operated without incident during the reporting period.

Water and Load Balance

A mine water balance computer simulation program is maintained using GoldSim software. Viewing the file requires the GoldSim 11.1 Player. An updated data file has been included with this report.

In addition a Total Dissolved Solids (TDS) load balance spreadsheet is provided for mine water areas and the Tailings Storage Facility. The spreadsheet data (flows and summary sections only) is listed in Appendix I of this report. An electronic file of the complete worksheet labeled "Red Dog Mine 2017 Water and Mass Balance Estimates.xlsx" is attached with the report.

The TDS load balance spreadsheet shows a negative TDS balance for the 2017 year, attributable to continuous wastewater treatment year round and a successful discharge season. The Tailings Storage Facility contained an estimated 3.337 billion gallons of free water (end of 2017) compared to 3.718 billion gallons for the previous year, a 10% reduction.

Approximately 773 million gallons was pumped from the Main Pit water to the Tailings Storage Facility during 2017. Main Pit water continues to be pumped year round to account for waste rock displacement in the pit. Main Pit water transferred to the Tailings Storage Facility accounted for the majority of TDS loading to the Tailings Storage Facility during 2017.

The Acid Rock Drainage (ARD) water collection system collected approximately 56 million gallons for 2017, slightly less than the previous year. Of this amount approximately 53 million gallons were treated in WTP1 or WTP3. The reduced volume collected was due to collection well sump being decommissioned during 2017. Options to replace the well sump or increase ARD collection capacity will be investigated during 2018.

An estimated 14,418 tonnes of TDS was removed from ARD water and 16,238 tonnes of TDS was pumped from the Main Pit to the Tailings Storage Facility during the year.

Significant reagents consumed for wastewater treatment during 2017:

- Total quantity of flocculant used in Waste Treatment Plant 2 (WTP2) and WTP1 was 99.4 metric tonnes, the majority being used in WTP2.
- Total quantity of lime used in WTP2 is not tracked individually, though the total lime used in WTP1, WTP2 and WTP3 was 10,928 metric dry tonnes.
- Total quantity of sodium sulfide used in WPT1 and WTP2 was 965.3 metric tonnes, utilized to precipitate cadmium.
- Total quantity of flocculants used in WTP3; None
- Quantity of any other chemicals used in significant quantities in WTP2; Gypsum 1,342.6 metric tonnes

Significant activities in mine water management

The Main Waste Dump cover test plot construction was completed 10/23/18. A total of 15 acres of synthetic liner and cover material has been installed. Monitoring of cover performance will be ongoing over the next 18 months.

- The 2017 13 acre project was delayed 23 days due to weather. The project was completed with no significant changes to the original design plan.
- The back dam and main dam piezometers were all installed with wireless acquisition and real time monitoring capabilities.

Figure 1 - Photos of MWD Synthetic Cover Project



Photo 1 – Looking west off MWD. Placing cover rock over the geocomposite.

Photo 2 – Looking northwest at the top of the MWD.



Photo 3 – Looking north, on upper surface of MWD. Drainage channel to the left.

Waste Rock Management

Quantities, placement locations and analysis of waste rock

Results of waste rock geochemical monitoring

Other than blast hole analyses, no additional geochemical monitoring was conducted on waste rock during the reporting period. Geochemical blast hole monitoring results are included within the *Waste Rock Production Summary* report listed in Appendix F of this report.

Visual monitoring of waste rock facilities

Weekly waste dump inspections were conducted on both inactive and active waste rock dumps with

no adverse findings noted. Dig face inspections were carried out on waste shots to confirm waste characteristics and suitability for designated stockpile locations. All waste material was placed in suitable waste dump locations. The primary waste dump sites used during the 4th quarter were the Main Pit Dump (MPD3, MPD4, and MPD5), Oxide / Main Waste Dump (Copper Waste Dump, Landfill, and Oxide Ore Stockpile), and Cold Storage North.

A total of 515,239 tonnes of waste rock were hauled from the Aqqaluk pit and a total of 873,052 tonnes of waste rock were hauled from Qanaiyaq pit.

Main Pit Dump Area

For the fourth quarter of 2017 a total of 1,185,048 tonnes were hauled to the Main Pit Dump area.

- 5.018 tonnes of Ikalukrok "Other Waste" were hauled to MPD3.
- 180,331 tonnes of Ikalukrok and Siksikpuk "Most Reactive Waste" were hauled to MPD4.
- 535,557 tonnes of Ikalukrok and mixed "Other Waste" were hauled to MPD4.
- 80,933 tonnes of Ikalukrok and Siksikpuk "Most Reactive Waste" were hauled MPD5.
- 383,209 tonnes of Ikalukrok, Kivalina, and mixed "Other Waste" were hauled to MPD5.

Oxide / Main Waste Dump Area

For the fourth quarter of 2017 a total of 170,767 tonnes were hauled to the Oxide / Main Waste Dump (MWD). The Copper Waste Dump was recently added on the northern edge of the MWD.

- 7,020 tonnes of Ikalukrok and Siksikpuk "Most Reactive Waste" were hauled to the Copper Waste Dump (CWD) storage area, which is a new dumping location located on the Main Waste Stockpile Area.
- 10,753 tonnes of Ikalukrok "Other Waste" were hauled to CWD.
- 2,280 tonnes of mixed "Most Reactive Waste" were hauled to the Landfill (LAN).
 3,999 tonnes of Ikalukrok "Other Waste" were hauled to LAN. 52,751 tonnes of Ikalukrok and Siksikpuk "Most Reactive Waste" were hauled to the Oxide Ore Stockpile (OXO).
 93,964 tonnes of Ikalukrok, Kivalina, and mixed "Other Waste" were hauled to OXO.

Cold Storage North

For the fourth quarter of 2017 a total of 2,785 tonnes of Ikalukrok and mixed "Most Reactive Waste" was hauled to the Cold Storage North waste dump (CSN).

Portable Crusher / Stemming Rock

For the fourth quarter, 3,974 tonnes of Ikalukrok "Most Reactive Waste" and 25,717 tonnes of Ikalukrok "Other Waste" were hauled to the Portable Crusher – which was placed near MPD4 during 2017. This material is used for projects and in-pit stemming use for blasting.

Weekly visual inspections of waste rock facilities were conducted by the Senior Geotechnical Engineer or their trained designee. No incidents or findings were noted for the reporting period.

Dig face inspections were carried out on waste shots to confirm waste characteristics and suitability for designated stockpile locations. All waste material was placed in suitable waste storage stockpiles.

Cover Material at Main Waste Stockpile

No cover material was stockpiled for the period. Table 2 lists amount of cover material stockpiled onsite.

Table 2 - Cover Material Amount

	Tonnes Hauled per Month		Total Tonnes	Tonnes	
Cover Stockpile Location	Oct	Nov	Dec	Report Period	Stockpiled
Ramp to Nowhere (RNC)	0	0	0	0	1,390,625
Oxide 2 Cover Dump (OX2)	0	0	0	0	39,694
Oxide Cover Dump (OCD)	0	0	0	0	27,880
North Oxide (NOX)	0	0	0	0	553,245
South Oxide Top Soil (SOT)	0	0	0	0	81,094
				0	2,092,538

Significant activities in waste rock management

No significant activities reported for the 4th quarter.

Tailings Management

Quantities and analysis of tailings

Table 3 depicts the dry tonnes of tailings generated and the average lead, zinc and iron concentrations in the tailings solids for the 4th quarter and summation and average concentrations for the 2017 report year.

Table 3 - Tailings Generated

			Analysis	
Month	Dry Tonnes Tailings	% Pb	% Zn	% Fe
Oct	269,309	2.1	3.2	7.1
Nov	205,840	2.5	3.0	8.2
Dec	244,923	2.9	3.1	8.1
Annual sum/avg.	3,070,336	2.2	2.9	7.6

Tailings Storage Facility and Main Pit Dump water elevation

Table 4 depicts the surveyed Tailings Storage Facility and Main Pit water levels during the reporting period. The current dam permits allow for a crest elevation of 986 feet amsl or 981 amsl freeboard. The Tailings Storage Facility water level for the 4th quarter was maintained below the freeboard limit. The Main Pit Dump was maintained below an elevation of 850 feet amsl.

Table 4 - Tailings Storage Facility and Main Pit water elevations

Tailing	s Storage Fa	cility Elevation	Main Pit Dump		Dump
Survey Date	TSF Feet MSL	Comment	Survey Date	MPL Feet MSL	Comment
Date	Elevation	Comment	Date	Elevation	Comment
10/6/2017	970.17	Weekly H2O	10/6/2017	840.23	Weekly H2O
10/11/2017	970.19	Weekly H2O	10/11/2017	840.29	Weekly H2O
10/18/2017	970.18	Weekly H2O	10/18/2017	840.54	Weekly H2O
10/25/2017	971.07	16* It wind	10/25/2017	841.40	16* It wind
11/1/2017	971.17	H2O Weekly	11/1/2017	842.09	H2O Weekly
11/8/2017	971.17	Due to snow, access to the tailings pond was blocked.	11/8/2017	841.96	Weekly H2O
11/14/2017	971.38	Weekly H2O	11/14/2017	841.91	Partially Frozen Weekly H2O
11/25/2017	972.16	Weekly H2O	11/25/2017	841.75	
11/30/2017	971.85	Weekly H2O	12/6/2017	838.87	
12/6/2017	972.10	Weekly H2O	12/14/2017	838.87	
12/14/2017	972.29	Weekly H2O	12/21/2017	N/A	Storm -unable to aquire
12/21/2017	N/A	Storm -unable to acquire.	12/30/2017	839.98	Ice
12/27/2017	972.65	ice			


Visual monitoring of tailings facilities


Visual monitoring inspections of the tailings storage facilities were completed during the 4th quarter. All systems operated as designed with no findings.

Significant activities in tailings management

Tailings were deposited several areas of the Tailings Storage Facility during the 4th quarter, mainly along the west and northwest portions of the Tailings Storage Facility.

Bathymetry surveys were completed June 15, 2017 for both the Tailings Storage Facility and the Main Pit. A bathymetry map for each area was generated and depicted in Figures 2 and 3.





Class III Municipal Solid Waste Landfill

Visual inspections were conducted at the landfill and random inspections conducted on bins of refuse waste prior to being hauled to the landfill. No incidents were reported during the 4th quarter.

Landfill Use Plan

For the 2018 year, refuse will continue to be placed on the existing 2017 lift while working toward the northern end of the cell. It is expected during the spring of 2018 a new lift will be started where refuse will placed at the southern end and progress in a northerly direction.

A waste management consultant was retained during the 4th quarter which will assist with enhancing Red Dogs recycling opportunities. The consultant is expected to be onsite for at least twelve months with the main goal of establishing a much more robust recycling program.

Quantities of inert solid waste for the reporting year

The quantity of inert solid waste (cover rock not included) placed in the landfill for 2017 was calculated at 15,962 cubic yards of uncompacted waste.

Significant activities in solid waste landfill

No significant activities occurred at the solid waste mine landfill during this reporting period.

Mining and Milling Activities

Mining quantities

Table 5 lists the tonnes of ore hauled to the mill stockpile each month during the reporting period. This does not include marginal ore which was placed within the Marginal Ore Stockpile.

Table 5 - Ore Mined

Date	Ore Mined, tonnes
Oct	336,633
Nov	226,271
Dec	371,680
Annual	4,014,895

Milling Quantities

Table 6 lists the tonnes of ore processed through the mill facilities each month during the reporting period.

Table 6 - Ore Processed through Mill

Date	Ore Milled, tonnes
Oct	394,233
Nov	282,301
Dec	348,474
Annual	4,269,909

Significant activities in mining and milling

There were no significant activities in mining and milling during the quarter.

Reclamation

Reclamation Activities

Area Disturbed and Reclaimed

Table 7 depicts new disturbed acreage for 2017. A map of the new (2017) and total disturbance areas is shown in Figure 5 – Red Dog Mine 2017 Disturbance. No areas were reclaimed during the reporting period. Any top soil recovered from newly disturbed areas was stockpiled for future use.

Table 7 - Area Disturbed in 2017

2017 Disturbance Area	Acres
Aqqaluk exploration sites	3.9
PAC dump expansion	1.2
Airport paving project material site	5.2
Total	10.3

Reclamation Research

Peter Johnson from Alaska Department of Environmental Resources (ADNR) was retained by Red Dog to initiate a new vegetation study on the Main Waste Dump. The study area comprises 6 small test plots located on the upper surface of the Main Waste Dump. The study involves variations of grass seed mixture, forbs, mulch application and fertilizer types and rates. The study commenced during June 2017 and will continue for the next several years.

Reclamation Monitoring

No monitoring was completed for the reporting year.

Significant reclamation activities

No reclamation activities took place during the 2017 reporting year.

Dust

Dust monitoring activities

The 2017 Risk Management Plan Annual Report is not yet completed. The report should be finalized by the 2nd quarter of 2017. A final report will be submitted when complete as Appendix J.

Wildlife


Wildlife interactions

No wildlife interactions occurred during this 4th quarter reporting period.

Financial Assurance

TAK increased the reclamation bond for Reclamation Plan Approval (F20169958) by \$4,466,800 to account for inflation based on the Anchorage Consumer price Index (CPI). The total bond amount is \$562,816,800. The adequacy of the bond is sufficient for current operations and conditions.

Figure 4 - Land Disturbance Map



2018 Mine Plan

A 2018 Mine Plan is included with the annual report and listed within *Appendix H: Red Dog One Year Mine Plan 2018*. References to grades have been redacted from the document to conform to with fiscal regulations.

The majority of the ore to be mined for the 2018 year is anticipated to come from the Aqqaluk pit with remaining amount of ore coming from the Qanaiyaq Pit.

Closing

Please accept this report as required under the State of Alaska Waste Management Permit No. 2016DB0002 and Reclamation Plan Approval F20169958. If there are any questions, please contact Frank Bendrick at (907) 754-5138 or myself at (907) 754-5272.

Based on information and belief formed after reasonable inquiry, I certify that the statements and information in and attached to this document are true, accurate and complete.

Sincerely,

Teck Alaska Incorporated

John Egan

Acting General Manager

cc: Tim Pilon, ADEC, Fairbanks;
Marie Steele, ADNR, Anchorage
Brent Martellaro, ADNR, Fairbanks
DNR.Water.Reports
Jim Vohden, ADNR
Audra Brase, ADF&G, Fairbanks

Lance Miller, NANA